CHITALDRUG DISTRICT.

THANGADI AND KAKKE BARKS.

Resale Notification dated 3rd October 1935.

It is hereby notified for the information of the intending purchasers that the Thangadi and Kakke barks contractors of the several Taluks (except Jagalur) of the Chitaldrug District, for the years 1935-37, having failed to execute agreements furnishing the required Security Deposit and sureties, etc., the right of collecting and removing the barks in all the Taluks except Jagalur, will be resold by public auction by the Revenue Sub-Division Officer, Chitaldrug Sub-Division, assisted by the District Forest Officer, Chitaldrug.

Place of sale .. .. .. District Forest Office, Chitaldrug.
Date and hour of sale .. .. .. 25th October 1935, 2 P.M.

For details of sale conditions, etc., please *vide* notification published on pages 874-876 of Part VI of the *Mysore Gazette*, dated 18th April 1935.

D. NARASIMHAMURTHI RAO,
District Forest Officer.

ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 24th September 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 29th October 1935, for providing sanitary fittings to the several wards of the Victoria Hospital, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by 31st December 1935.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for providing sanitary fittings to the several wards of the Victoria Hospital, Bangalore," in default of which, the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Abstract estimate of quantities of work for providing sanitary fittings to the several wards of the Victoria Hospital, Bangalore.

Sl. No.	Particulars	Per	Quantity
	LABOUR.		
	(a) *Soil, Waste and Water Connections.*		
1	Providing 4" C.I. soil pipe with specials, such as bends, offsets, junctions, etc., laying and jointing with lead	R.ft.	398
2	Do 3" pipes as above	,,	72

Sl. No.	Particulars	Per	Quantity
3	Providing and fixing 4″ boiler tube 16′ long with necessary C. I. soil specials and pipes and support with masonry or clamps and providing and fixing 4″ zinc ornamental cowl and painting pipe, etc., complete	Each	9
4	Providing and fixing 3″ C. I. trap with cement concrete bed and constructing cement concrete cistern, cement plastering providing and fixing 6″ dia. C. I. grating, etc., complete	Each	2
5	Constructing ground sink with 3″ cement concrete bed and cement plastering	,,	4
6	Breaking and removing red tiles or slabs and providing, 3″ chunam concrete bed in closet area and cement plastering, if necessary	,,	28
7	Stone wall bore and redoing in cement mortar	,,	41
8	Cornice bore and redoing with cement mortar including scaffolding	,,	8
9	Terrace bore and redoing with cement mortar	,,	4
10	Fixing water closets and Hindustani closet set complete	,,	28
11	Removing Cudapah slab or tiles and relaying with chunam mortar, 3″ concrete bed including replacing damaged ones and pointing with cement	S. ft.	376
12	Scraping old paint and painting two coats of white-lead and 2 coats of white enamel paint to C. I. cisterns and all connection pipe	Each	28
13	Dismantling open drain and reconstructing with cement mortar and cement plastering complete	,,	26
14	Providing and fixing ¾″ and ½″ lead pipe bending and fixing with wiped solder joints for water closets and Hindustani closets connections	,,	52
15	Providing and fixing ½″ nickle-plated stop cock with unions	Each	28
16	Providing and fixing ½″ nickle plated bib cock	,,	28
17	Water connection with ¾″ and ½″ G. W. pipe with fittings, laying and jointing, wall bore, wall and floor grooving and redoing, etc., complete up to fittings	Each connection	56
18	Providing and fixing 2″ anti-syphon pipe with specials including lead pipe connection with solder joints and brass thimbles and tail pieces, wall bore, wall grooving, etc., up to roof level and providing and fixing 2″ zinc ornamental cowl	Each	28
19	Providing and fixing white glazed tiles (English Make) in cement mortar and pointing with white cement	S.ft.	392
20	Breaking and removing roofing tiles and reepers and redoing and making cement concrete bandage after fixing vent pipes	Each	3
21	Providing 2″ reinforced concrete partition including cost of repairing and altering existing door shutters with providing and fixing bolts, hinges, pad locks, etc., complete and cement plastering the partitions on both sides complete	S.ft.	226
	(b) Drainage arrangements.		
1	Providing 4″ S. W. pipe, laying and jointing in cement mortar, earthwork excavation and refilling and testing, etc., complete	R.ft.	416
2	Do 6″ pipe as above	,,	202
3	Providing 6″×4″ S. W. gully trap with grating and fixing in cement mortar concrete, constructing cistern complete and providing and fixing hinged lid and frame, if necessary	Each	14
4	Providing and fixing 10″×10″ C. I. grating in cement mortar	,,	4
5	Manhole bore and redoing and making drain in cement mortar	,,	21
6	Constructing inspection chamber 2½′ dia. inside with earth excavation cement concrete bed 9″ thick, burnt brick in cement mortar 9″ thick wall, cement plastering, making drains providing and fixing 21″ dia. C. I. manhole cover and frame complete up to 3′ depth	,,	3
7	Do manhole of 4′ dia. inside and all as per above details up to 4′ height	,,	5
8	Constructing ordinary cistern and providing and fixing 10″×10″ C. I. grating	,,	2

K. S. HUTCHA RAO,
Sanitary Engineer in-charge.